



KEY :-

- Proposed footpath construction Type 1 to a depth of 70mm. Surface course - 20mm Binder course - 50mm Total Area = 28m² or 2m².
- Proposed footpath construction Type 1 to a depth of 170mm Surface course - 20mm Binder course - 50mm Sub-base - 100mm Total = 50m² or 9m².
- Proposed footpath construction Type 1 to a depth of 240mm. Tactile slab - 65mm Sand bed - 25mm Sub-base - 150mm Total = 22m² or 6m².
- Proposed Type 1 (V4) guardrailing to be painted black RAL 9005. Total = 10 panels (20m in length).
- Proposed Transition kerbs Total = 10m.
- Proposed Dropped kerbs Total = 10m.
- Proposed edging kerbs Total = 30m.
- Proposed 400 x 400 Buff tactile paving slabs Total = 50 paving slabs.
- Proposed Road Signs and Posts.
- Proposed Marshalls Pencil Bollards Total = 3 units.

H:\RoadSafetyUnit\SRTS\Safer Routes to School\SRTS Stratford\Temple Grafton CofE Primary School\Drawings\Draft\SSZ100-300 Temple Grafton CofE Primary School - Site Location Plan.dwg



COMMUNITIES
 Monica Fogarty
 Strategic Director for Communities
 Graeme Fitton BSc, MSc, C.Eng, MICE.
 Head of Transport for Warwickshire

PO Box 43, Shire Hall
 Warwick, CV34 4SX
 Tel: (01926) 410410
 Fax: (01926) 491665

www.warwickshire.gov.uk
<mailto:communities@warwickshire.gov.uk>

NOTES

Based on Ordnance Survey mapping with the permission of the Controller of HMSO
 © Crown Copyright and database right 2011. Ordnance Survey 100019520. All rights reserved.
 Unauthorised reproduction infringes copyright and may lead to prosecution or civil proceedings. Warwickshire County Council.

REV	DATE	BY	CHK	AMENDMENT
A	8/11/16	CR	GS	Minor changes after site inspections.
-	--/--	-	-	-
-	--/--	-	-	-
-	--/--	-	-	-
-	--/--	-	-	-

Drawing title	Drawn by	Checked by
Temple Grafton Primary School Temple Grafton Kerbs, footways & Paved areas - SERIES 1100	CR	GS
	Date	September 2016
	Scale	As shown @ A3
Project title	Drawing number	
SSZ STRATFORD	SSZ100-304A	